



TIPTON FIRE DEPARTMENT TIPTON, IOWA

TECHNICAL SPECS

- Ford F 550 2- Door XL Supercab Cab 4 x 4 Chassis
- Ford 6.0 L Powerstroke 250 HP Diesel Engine
- Ford TorqShift Automatic Transmission
- Powerall 5000 Watt Generator – Under Hood
- 3/16" Heavy Duty Flatbed Body
- Two (2) Firefighter Stanchions, one (1) on each side.
- Two (2) treadplate compartments left side with ROM style doors.
- Two (2) treadplate compartments right side with ROM style doors.
- Walk-thru platform behind the cab with Mansaver Bars
- 300 Gallon UPF Defender 1 Poly Tank
- 20 Gallon Foam Tank
- Hale HPX400-BD26 Diesel Pump
- PowerArc Warning light Package
- Code 3 MX700 Series Lightbar mounted on the headache rack
- Hannay Booster Reel 4038-17-18
- Electric Cord Reel in rear passenger compartment
- Ramsey QM 9000 Winch
- Front and Rear hitch mounts.
- Electrically controlled spray booms in front bumper
- Preconnect Hose Tray in upper right side compartment
- Four (4) Walk-Away air pak brackets
- Turtle tile on floor
- 7'-4" Overall Height
- 22' Overall Length
- 60" Cab-to-Axle
- 161.8" Wheelbase
- 7,000 FAWR
- 13,660 RAWR
- 19,500 GVWR



Alexis Fire Equipment Company would like to thank the Tipton Fire Department for their business.

Alexis Fire Equipment Company
109 East Broadway
Alexis, Illinois 61412